330 Ton Portable Air Cooled Screw Chiller

Mahila Air

Mobile Air

Mobile Air Air Cooled Screw Chiller packages are self-contained and specifically engineered to provide flexible, temporary chilled fluid for commercial and industrial air conditioning and process cooling applications. Package includes integrally located pump matched specifically to range of operation, piping (with pump bypass), triple-duty valves, chilled fluid fittings and in-line water strainers. The chiller package is permanently mounted on an air ride trailer. These on-board features allow for quick delivery and minimal installation time.



- SP NF Disconnect with system circuit breakers
- Louvered panel enclosure (condenser coil only)
- Flow switch with flow safety interlock

Package Features


- 48' Air-ride flatbed trailer
- 40 HP Integral pump package (standalone/booster)
- Pump bypass option
- 6" Strainer with pump and bypass option
- 6" Triple-duty valve with pump and bypass option
- 120V-15A Convenience outlet
- 120V Extension cord shore power option

Quick delivery and minimal installation time when you need temporary cooling.

For more information contact:


Mobile Air


1-800-596-0800



Minimum Clearances: units side by side: 12 ft, control panel to wall: 5 ft, side to wall: 8 ft, front to wall: 8 ft. Install unit on flat level surface.

Cooler Water Pressure Drop





General

Chiller Model Number	YCAS0330 ⁽¹⁾
Ambient Operating Range	0-125°F
Chilled Water Setpoint Limits	40-55°F
Refrigerant Circuits	3
Equipment Insurance Value	\$300,000
(1) See Johnson Controls YCAS Engineering Gu	ide for additiona

⁽i) See Johnson Controls YCAS Engineering Guide for additiona chiller specifications

Dimensions (Trailer Mounted)

Length	48' 0"
Width	8′ 6″
Height	13′ 6″
Total Weight (with trailer)	34,662 lbs

Electrical

Single Point Power Supply	460V / 3Ø / 60Hz
Connections (3 per Ø)	Series 16 Cam Type
Running Load Amps	612A ⁽²⁾
Minimum Circuit Ampacity	659A ⁽²⁾

⁽²⁾ Includes 40HP pump (45.7A)

Evaporator Flow

Minimum	255 GPM
Nominal	792 GPM
Maximum	800 GPM
Fluid Connections (ground level)	6", Grooved
Maximum Water Side Pressure	150 PSIG